




March 28, 2018

- | | | |
|--|---|---|
|  County Boundary |  Subdivision Lot Numbers |  Tax Parcels Alternate Key |
|  Street Names |  Address Locations |  Tax Parcels |
|  Local Streets |  Property Name |  Surrounding Counties |



Lake County Board of County Commissioners

HOWEY CENTRAL AVE PARKING RECONSTRUCTION						
Vendor Name: CW Roberts Contracting, Inc.						
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost	
1	Mobilization, General Conditions and MOT	LS	1	\$ 11,500.00	\$ 11,500.00	
2	Roadway/Parking Lot/Trail & Prepare Compacted Sub Base	SY	296	\$ 4.00	\$ 1,184.00	
3	Finish Grading	SY	385	\$ 4.00	\$ 1,540.00	
4	Excavation, General	CY	100	\$ 18.00	\$ 1,800.00	
5	Limerock 6" Base	SY	296	\$ 15.00	\$ 4,433.33	
6	Reclaimed Asphalt Pavement Base (Reclaim) 6" to 8"	SY	1121.00	\$ 5.50	\$ 6,165.50	
7	Removal of Existing Asphalt Pavement	SY	1121	\$ 12.00	\$ 13,452.00	
8	Asphalt Pavement Superpave - (9.5)	TN	125	\$ 110.00	\$ 13,750.00	
9	Concrete Curb & Gutter Remove	LF	377	\$ 13.00	\$ 4,901.00	
10	Concrete Curb, Type D	LF	750	\$ 16.00	\$ 12,000.00	
11	Concrete Sidewalk 4"	SY	83	\$ 45.00	\$ 3,735.00	
12	Concrete Sidewalks Remove	SY	260	\$ 15.00	\$ 3,900.00	
13	Pavers, Architectural Sidewalk	SY	360	\$ 120.00	\$ 43,200.00	
14	Detectable Warning on Walking Surface, Retrofit	SF	50	\$ 30.00	\$ 1,500.00	
15	Sod- Bahia	SY	178	\$ 5.00	\$ 890.00	
16	Single Post Sign, F & I, Less than 12 ft.	AS	6	\$ 250.00	\$ 1,500.00	
17	Painted Pavement Markings, Standard, White, Solid, 6"	LF	1780	\$ 0.40	\$ 712.00	
18	Thermoplastic, Standard, White, Solid, 12"	LF	148	\$ 3.00	\$ 444.00	
19	Thermoplastic, Standard, White, Solid, 24"	LF	66	\$ 5.00	\$ 330.00	
TOTAL ESTIMATE					\$ 126,936.83	

Base Bid

CONSTRUCT 15' WIDE ALLEY BETWEEN SR 19 AND SOUTH DIXIE DRIVE					
HOWEY IN THE HILLS, FL					
Vendor Name:		CW Roberts Contracting, Inc.			
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
101-002-1	Mobilization and General Conditions	LS	1	\$ 7,600.00	\$ 7,600.00
101-002-02	Clear and Grubb	LS	1	\$ 2,000.00	\$ 2,000.00
120-001.401	Finish Grading/Subgrade compaction	SY	558	\$ 4.00	\$ 2,232.00
120-01.01.01	Excavation, General	CY	200	\$ 20.00	\$ 4,000.00
210-02.01.01	Limerock 6" Base	SY	558	\$ 15.00	\$ 8,370.00
334-72.01.02	Asphalt Pavement Superpave - (9.5) 1.5"	TN	45	\$ 110.00	\$ 4,950.00
700-20.11	Single Post Sign, F & I, Less than 12 ft.	AS	3	\$ 250.00	\$ 750.00
710-011.125	Painted Pavement Markings, Standard, White, Solid 24"	LF	15	\$ 2.50	\$ 37.50
0710-11.170	Painted Pavement Markings, Standard, White, Arrows	EA	4	\$ 50.00	\$ 200.00
TOTAL ESTIMATE					\$ 30,139.50

CONSTRUCTS THE 15' WIDE ALLEY FROM SR19 TO DIXIE DR.

A

CONST DIAGONAL PARKING ON CLARK PROPERTY					
HOWEY IN THE HILLS, FL					
Vendor Name:		CW Roberts Contracting, Inc.			
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
101-002-1	Mobilization and General Conditions	LS	1	\$ 3,500.00	\$ 3,500.00
101-002-02	Clear and Grubb	LS	1	\$ 2,000.00	\$ 2,000.00
110-004.01	Install New Concrete Wheel Stop	EA	15	\$ 35.00	\$ 525.00
120-001.401	Finish Grading/Subgrade compaction	SY	356	\$ 4.00	\$ 1,424.00
210-02.01.01	Limerock 6" Base	SY	356	\$ 15.00	\$ 5,340.00
334-72.01.02	Asphalt Pavement Superpave - (9.5) 1.5"	TN	30	\$ 110.00	\$ 3,300.00
520-02.01.05	Concrete Curb, Type D	LF	180	\$ 16.00	\$ 2,880.00
710-011.111	Painted Pavement Markings, Standard, White, Solid, 6"	LF	600	\$ 0.40	\$ 240.00
TOTAL ESTIMATE					\$ 19,209.00

widens Alley construction to
Dr. Clark's property to provide
Parking

B

CONST PARKING LOT ON CITY PROPERTY BTW CLARK AND MARKET					
HOWEY IN THE HILLS, FL					
Vendor Name:		CW Roberts Contracting, Inc.			
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
101-002-1	Mobilization and General Conditions	LS	1	\$ 3,500.00	\$ 3,500.00
101-002-02	Clear and Grubb	LS	1	\$ 2,000.00	\$ 2,000.00
110-004.01	Install New Concrete Wheel Stop	EA	5	\$ 35.00	\$ 175.00
120-001.02	Roadway/Parking Lot/Trail & Prepare Compacted Sub Base	SY	122	\$ 4.00	\$ 488.00
120-01.01.01	Excavation, General	CY	50	\$ 20.00	\$ 1,000.00
210-02.01.01	Limerock 6" Base	SY	122	\$ 15.00	\$ 1,830.00
334-72.01.02	Asphalt Pavement Superpave - (9.5) 1.5"	TN	15	\$ 110.00	\$ 1,650.00
710-011.111	Painted Pavement Markings, Standard, White, Solid, 6"	LF	120	\$ 0.40	\$ 48.00
TOTAL ESTIMATE					\$ 10,691.00

CONSTRUCTS THE SMALL PARKING LOT SHOWN BETWEEN THE MARKET AND DR. CLARKS OFFICE

C

EXPAND HC PARKING BEHIND CLARK					
HOWEY IN THE HILLS, FL					
Vendor Name:		CW Roberts Contracting, Inc.			
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
101-002-1	Mobilization and General Conditions	LS	1	\$ 1,000.00	\$ 1,000.00
110-004.01	Install New Concrete Wheel Stop	EA	2	\$ 35.00	\$ 70.00
120-001.401	Finish Grading/Subgrade compaction	SY	50	\$ 4.00	\$ 200.00
120-01.01.01	Excavation, General	CY	20	\$ 20.00	\$ 400.00
210-02.01.01	Limerock 6" Base	SY	50	\$ 15.00	\$ 750.00
334-72.01.02	Asphalt Pavement Superpave - (9.5) 1.5"	TN	10	\$ 110.00	\$ 1,100.00
700-20.11	Single Post Sign, F & I, Less than 12 ft.	AS	2	\$ 250.00	\$ 500.00
710-011.111	Painted Pavement Markings, Standard, White, Solid, 6"	LF	100	\$ 0.40	\$ 40.00
TOTAL ESTIMATE					\$ 4,060.00

Adds To The Existing Asphalt
Behind Dr. Clark's Office
To The Edge of The Proposed
Alley Construction.

D

EXTEND DIXIE DRIVE PARKING TO BACK OF LIBRARY					
HOWEY IN THE HILLS, FL					
Vendor Name:		CW Roberts Contracting, Inc.			
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
110-004.01	Install New Concrete Wheel Stop	EA	12	\$ 35.00	\$ 420.00
120-001.02	Roadway/Parking Lot/Trail & Prepare Compacted Sub Base	SY	192	\$ 4.00	\$ 768.00
120-01.01.01	Excavation, General	CY	50	\$ 20.00	\$ 1,000.00
210-02.01.01	Limerock 6" Base	SY	192	\$ 15.00	\$ 2,880.00
334-72.01.02	Asphalt Pavement Superpave - (9.5) 1.5"	TN	20	\$ 110.00	\$ 2,200.00
520-02.01.05	Concrete Curb, Type D	LF	65	\$ 16.00	\$ 1,040.00
700-001.40	Highway Signing-Single Post Sign, Install-Stop Sign (R1-1)	EA	1	\$ 250.00	\$ 250.00
710-011.111	Painted Pavement Markings, Standard, White, Solid, 6"	LF	400	\$ 0.40	\$ 160.00
TOTAL ESTIMATE					\$ 8,718.00

Extends The Parking Construction.
 Along Dixie from The Base Bid
 Limits To The Back of The
 Library

E

DELETE DECORATIVE SW, INSTALL CONC SIDEWALK					
Vendor Name: CW Roberts Contracting, Inc.					
Item #	Description	Unit of Measure	Est Qty	Unit Price	Extended Cost
11	Concrete Sidewalk 4"	SY	122	\$ 45.00	\$ 5,490.00
13	Pavers, Architectural Sidewalk	SY	-122	\$ 120.00	\$ (14,640.00)
TOTAL ESTIMATE					\$ (9,150.00)

Deletes The Decorative Sidewalk
 And Installs A Concrete Sidewalk
 Between Dixie Drive And
 Dr. CLARKs office.